GOVERNMENT OF WEST BENGAL
Office of the Chief Medical Officer of Health,
Department of Health & Family Welfare, District Health & Family Welfare Samity,
1st Floor, Engineering Wings, District Administrative Building, Hospital Road,
Post & Dist.- Jalpaiguri Tele-Fax No. 03561-22538/225394, Email: dpmujpg@gmail.com

NOTICE INVITING QUOTATION DHFWS/CW-02 of 2025-26

Memo No: - DHFWS/579/25 Dated: 08/07/25

Sealed quotation for seeking of lowest rate (percentage rate) against the work of "**Supply and erection S.T. Poles for carring of overhead Power cable for Block Public Health Unit under Sulkapara Rural ospital, Nagrakata block, Jalpaiguri. (Additional work).**" is hereby invited by the CMOH & Secretary under Department of Health & Family Welfare Samity, Jalpaiguri from eligible Agencies (as per Terms and Conditions applied) as per particulars below and will be received by the Undersigned up to the time specified are therein and will be opened thereafter.

Sl no.	Name of the work	Total Estimated Amount (Rs.)	Completion of work
1.	Supply and erection S.T. Poles for carring of overhead Power cable for Block Public Health Unit under Sulkapara Rural ospital, Nagrakata block, Jalpaiguri. (Additional work).	67480 /-	07 days

The last date of Quotations received will be on 16.07.2025 within 04:00 P.M. and will be on same day 16.07.2025 at 04:30 PM.2025

Terms & Condition:-

1. Agencies will have to submit photo copies of valid Trade License, P.Tax Certificate, PAN Card No., I.T. Clearance Certificate, GST Registration, MOU (optional), Electrical Contractor License, Electrical SSC and documents of credential certificate having at least of 40% of gross estimated amount of work for the last 5 years along with the quotation application, Original papers may also be verified (If necessary) as per requirement.
2. Quotation rate (in a percentage i.e. below / above / At par) of the estimate amount should be submitted at the letter pad of the agency incl. all taxes, GST, L.cess etc. as per govt. rules.
3. The total work should be done to the base on schedule of work.
4. The work should be done as per specified items.
5. Any defective & below quality materials should be replaced by the agencies/suppliers within 24 hours (Twenty four hours) in his own cost.
6. Security deposit, Labour Welfare Cess @1% (One Percent), TDS etc. of the gross bill value of work will be deducted from the bill.
7. Security deposit will be kept 1(one) year from the date of completion of work.
8. The total liabilities of contractor's from this end will be closed after receiving of final bill.
9. The work area should be totally cleaned after completion of work and all Contingencies should be removed before submission of final bill.
10. Payment for the work will be made on availability of fund.
11. Warranty & Service should be provided by the supplier as per warranty declared by the manufacturer.
12. If the office happens to be closed on any specified date due to some unforeseen reason, the next working day will be considered for the purpose.

The authority reserves the right to reject or cancel any quotation at any time without assigning any reason thereof.

O/C

CMOH & Secretary,
Dist. Health & Family Welfare Samiti
Jalpaiguri
08/07/25

Memo No: - DHFWS/579/25 Dated:- 08/07/25

Copy forwarded for information and nrcessary action to:

1. The District Magistrate Jalpaiguri.
2. The Deputy CMOH – I/II/ III / IV , CMOH office, Jalpaiguri.
3. The AO, CMOH office, Jalpaiguri.
4. The BMOH, Nagrakata block, Jalpaiguri.
5. The AE / SAE / BME, CMOH office, Jalpaiguri.
6. The DAM, CMOH office, Jalpaiguri.
7. Notice Board of the undersigned office.
8. The IT Personal, Swasthya Bhavan , Kol-91 with a request to upload the Notice in the Departmental Web Publishing www.wbhealth.gov.in
9. The DSM, Jalpaiguri CMOH office with a request to upload the Notice in the departmental website www.jalpaigurihealth.com

O/C

CMOH & Secretary,
Dist. Health & Family Welfare Samiti
Jalpaiguri

08/07/25

Estimate

Name of Work :- Supply and erection S.T. Poles for carring of overhead Power cable for Block Public Health Unit under Sulkapara Rural ospital, Nagrakata block, Jalpaiguri. (Additional work).

Sl. No.	Description of Item	Qty	Unit	Rate (INR)	Amount (INR)
1	Supplying of 9 Mtr. long S.T. pole (Designation -4IO SP- 28) of weight 113 kg. length of the Section is Bottom section - 5 mtr., Middle section -2 mtr. and Top section -2mtr. and Outside Dia. & Thickness of section are Bottom- 139.7x5.4mm, Middle- 114.3x3.65 mm and Top88,9x3.2Smm. **Non-schedule.**	3	nos.	11590.00	34770.00
2	Erection of Single Steel Tubular Pole of length as given below with/without sole plate & Cap etc. in CC foundation(Proportion and dimension indicated below), having 6OOx60Ox150 mm thick CC (4:2:LI base block below sole plate/pole with hard jhama metal including CC (6:3:1) muffing 0.30 mts. dia and 0.30 mts. above ground level including 3 mm thick neat cemented finish and GI earth bolt after making drilled holes etc. on pole & carriage ol pole upto 1.6 Km from Store to work-site including filling up the excavated earth pit with shifted soil and ramming properly.**[PWD/GS Page No.: HI Item No.: 1]**	3	per pole	3033.00	9099.00
3	Extra on items 1& 2 above, for providing CC (6:3:1) base block (around the pole) dimension 0.45x0.45x0.60 mt. above ground level, neatly cemented finish (3 mm thick), at the base pole (in lieu of CC mulling) incl. drilled hole in pole suitable for alkathene/polythene entry, for street light wiring, without loop Box. **[PwD/GS Page No.: HI Item No.: 3,b,iii]**	3	item	533.00	1599.00
4	Painting of Steel Tubular Pole of lengths and no. of coats of paint, as given below with ready mixed paint/primer of approved make, and brand incl. preparation of surface by sand paper/emery paper, cleaning etc. for receiving fresh coat of paint **[PWD/GS Page: H-2 Item: 7 /AI Upto 9.0 mtr. long pole.**				
	a) One coat of red lead./Zinc chromate priming	3	per pole	210.00	630.00
	b) Ist coat of synthetic enamel paint over the primer	3	per pole	161.00	483.00
	c) 2nd coat of svnthetic enamel oaint over the Ist coat	3	per pole	147.00	441.00
5	Earthing with 5O mm dia GI pipe 3.64 mm thick x 3.04 Mts. long and 1 x 4 SWG GI (Hot Dip) wire (4 Mts. long), 13 mm dia x 80 mm long GI bolts, double nuts, double washers incl. S & F 15 mm dia QI pipe protection (1 Mts. long) to be filled with bitumen partly under the ground level and partly above ground level driven to an average depth of 3.65 Mts. below the ground level as below ISI-M.**[PwD/GS Page: G-I Item: 2(a)]**	3	nos.	1465.00	4395.00
6	Excavation of soil for installation of Earth Electrode and filling & ramming. (a) For Soft Soil. **[PwDi GS Page: G-I Item: 1]**	9	cu.m	230.00	2070.00
7	Extra for treatment of soil by using salt & charcoal or coke for plate electrode **[PwD/GS Page: G-2 Item: 3(b)**	3	item	568.00	1704.00
				Total Amount in Rs.	**55191.00**
				Add 7% District Charge on Scheduled Amount (Sl no. 2-7) in Rs.	**1429.47**
				Total Amount with District Charge in Rs.	**56620.47**
				Add 18% GST in Rs.	**10191.68**
				Total Amount with GST in Rs.	**66812.15**
				Add CESS @ 1% in Rs.	**668.12**
				Total Amount with L.CESS	**67480.28**
				Total amount in Rs.	**67480**
				Say	**67480.00**

Rupees Sixty Seven Thousand Four Hundred Eighty only

01/07/2025
Sub-Asstt. Engineer
(Water)
N.H.M.

02/07/25
Assistant Engineer
NHM, Jalpaiguri

Dy. Chief Medical Officer of Health-I
JALPAIGURI

Chief Medical Officer of
Health & Secretary
District Health & Family
Welfare Samiti, Jalpaiguri

7. Purchase of electronic items like TVs, cameras etc. and
5. Purchase of IT hardware: (the
guidelines)