GOVERNMENT OF WEST BENGAL
Office of the Chief Medical Officer of Health,
Department of Health & Family Welfare, District Health & Family Welfare Samity,
1st Floor, Engineering Wings, District Administrative Building, Hospital Road,
Post & Dist.- Jalpaiguri Tele-Fax No. 03561-22538/225394, Email: dpmujpg@gmail.com

NOTICE INVITING QUOTATION DHFWS/CW-03 of 2025-26

Memo No: - DHFWS/607/25 Dated: 14/07/25

Sealed quotation for seeking of lowest rate (percentage rate) against the work of "**Repairing of Air Conditioning machines of Food safety officer, Ayush, Conferrence room, Quality Assuarance Unit, Dy-CMOH-III under Jalpaiguri CMOH office.**" is hereby invited by the CMOH & Secretary under Department of Health & Family Welfare Samity, Jalpaiguri from eligible Agencies (as per Terms and Conditions applied) as per particulars below and will be received by the Undersigned up to the time specified are therein and will be opened thereafter.

Sl no.	Name of the work	Total Estimated Amount (Rs.)	Completion of work
1.	Repairing of Air Conditioning machines of Food safety officer, Ayush, Conferrence room, Quality Assuarance Unit, Dy-CMOH-III under Jalpaiguri CMOH office.	85,114 /-	15 days

The last date of Quotations received will be on 22.07.2025 within 04:00 P.M. and will be opened on 22.07.2025 at 04:30 PM.2025

Terms & Condition:-

1. Agencies will have to submit photo copies of valid Trade License, P.Tax Certificate, PAN Card No., I.T. Clearance Certificate, GST Registration, Electrical Supervisory Certificate, Electrical Contractor Licence and documents of credential certificate having at least of 40% of gross estimated amount of work for the last 5 years along with the quotation application, Original papers may also be verified (If necessary) as per requirement.
2. Quotation rate (in a percentage i.e. below / above / At par) of the estimate amount should be submitted at the letter pad of the agency incl. all taxes, GST, L.cess etc. as per govt. rules.
3. The total work should be done to the base on schedule of work.
4. The work should be done as per specified items.
5. Any defective & below quality materials should be replaced by the agencies/suppliers within 24 hours (Twenty four hours) in his own cost.
6. Security deposit, Labour Welfare Cess @1% (One Percent), TDS etc. of the gross bill value of work will be deducted from the bill.
7. Security deposit will be kept 1(one) year from the date of completion of work as defect liability of work.
8. The total liabilities of contractor's from this end will be closed after receiving of final bill.
9. The work area should be totally cleaned after completion of work and all Contingencies should be removed before submission of final bill.
10. Payment for the work will be made on availability of fund.
11. Warranty & Service should be provided by the supplier as per warranty declared by the manufacturer.
12. If the office happens to be closed on any specified date due to some unforeseen reason, the next working day will be considered for the purpose.

The authority reserves the right to reject or cancel any quotation at any time without assigning any reason thereof.

14/7/25

CMOH & Secretary,
Dist. Health & Family Welfare Samiti
Jalpaiguri

14/07/25

ESTIMATE

Name of Work:- Repairing of Air Conditioning machines of Food safety officer, Ayush, Conferrence room, Quality Assuarance Unit, Dy-CMOH-III under Jalpaiguri CMOH office.

SL. NO	DESCRIPTION	QTY.	UNIT	RATE (Rs.)	AMOUNT (Rs.)
1	Supply & fixing of New Rotary type compressor of 1.5TR capacity.(make-Hitachi/ Daikin / Emerson. (Food safety officer, Ayush, Dy.CMOH-III)	3	nos.	10212.00	30636.00
2	Supply and Fixing Fan Runner motor (Indooor) for 1.5TR Split type AC machine (make-Hitachi / Daikin /Emerson.	1	nos.	1802.00	1802.00
3	Supply and Fixing Fan motor (Outdooor) for 1.5TR Split type AC machine(make-Hitachi / Daikin / Emerson.	4	nos.	1527.00	6108.00
4	Supply and Fixing Air Conditioner Fan Blade for 1.5TR Split type AC machine (make-Hitachi / Daikin /Emerson.	4	nos.	1100.00	4400.00
5	Supply & Fixing of 5/8" and 1/4" copper refrigerant pipes with nitrail rubber thermal insulation, 2 run 2.5 Sqmm 3 core unarmored copper cable and best quality PVC drain pipe incl fixing arrangement complete with high quality saddle in all respect upto 2.5TR split type AC machine.	23	mtr	1025.00	23575.00
6	Supply & Charging of R-32/ R-410A refrigerant Gas.	5.5	kg	890.00	4895.00
				SUM Rs.	***71416.00***
				Add GST@18%	***12854.88***
				Sub Total	***84270.88***
				Add L.W.C @ 1%	***842.71***
				TOTAL Rs.	***85113.59***
				Say Rs.	***85114.00***

Sd/-
CMOH & Secretary
Jalpaiguri